




PROJECT IMPLEMENTATION CONSIDERATIONS FOR THE CALIFORNIA WATERFIX

San Luis Delta Mendota Water Authority
July 19, 2017




CALIFORNIA WATER FIX- OVERALL PROGRAM





TUNNEL PORTIONS OF PROGRAM





MAIN TUNNELS


- 100 year life
- Twin bore main tunnels
- 150 ft below grade
- Concrete segmental liner
- Pressurized face Tunnel Boring
 Machine construction
- 45 ft excavated diameter
- 40 ft finished internal diameter



Photo Courtesy: Port of Miami Tunnel




LARGE DIAMETER TUNNEL BORING MACHINE PROJECTS





GEOTECHNICAL PROFILE AT TUNNEL DEPTH



Note: Over 200 borings/CPTs completed



PROGRAM FACTS

- 700,000 tunnel segments
- 23 million cubic yards of excavated tunnel material
- 10-12 Tunnel Boring Machines operating simultaneously
- 195 Mega Watts of power required for Tunnel Boring Machines
- Existing levees protect project sites
- Limited highway access in Delta




TYPICAL TUNNEL SEGMENTS AND LINED TUNNEL







REUSABLE TUNNEL MATERIAL



- Preliminary level of testing (DWR Report)
 - Sterile material
 - Suitable for engineering fill
- Stockpiles at 6-14 ft
- Existing restoration uses
 - SFPUC Bay Tunnel Bair Island
 - London Crossrail Wallasea Island





RIVER INTAKES





PROTECTING FISH







CLIFTON COURT PUMP PLANTS





PROGRAM ESTIMATES


	Amount (\$ billions)
Total	\$ 14.94
PM/CM/Engineering	\$ 1.91
Tunnels/Shafts Construction	\$ 6.82
Remaining construction	\$ 2.68
Land Acquisition	\$ 0.15
Contingency (approx. 36% for tunnels/shafts and remaining construction)	\$ 3.38

Program Estimate in 2014 Dollars



DESIGN AND CONSTRUCT ENTERPRISE

ORGANIZATIONAL STRUCTURE



8

DCE PROGRAM SCHEDULE





REVIEW OF OTHER MEGA-TUNNEL PROJECTS


- The Eurasia Tunnel Turkey
- ✓ Lee Tunnel London
- ✓ Port of Miami Tunnel Florida
- ✓ East Side Access New York
- ✓ Blue Plains Tunnel Project District of Columbia
- ✓ Bay Tunnel San Francisco
- ✓ Willamette River Combined Sewer Outfall Program Portland
- ✓ Gotthard Base Tunnel Swiss Alps
- ✓ SR-99 Alaskan Way Replacement Seattle
- ✓ = projects visited by program team



THE EURASIA TUNNEL – TURKEY











THE EURASIA TUNNEL – TURKEY

- Transportation Tunnel
 40 ft Internal Diameter (ID) x 2.1
 miles
- 320 ft deep
- Completed Dec 2016
 - 3 months ahead of schedule
- Challenges
 - Complex geology, seismically active zone, and high groundwater pressure





LEE TUNNEL - LONDON









LEE TUNNEL - LONDON

- 23.6 ft ID x 4.3 mile Combined Sewer Outfall (CSO) Tunnel
- 160 ft deep
- Completed December 2015
 - On schedule
 - Within budget
- Challenges
 - Groundwater contamination,
 complexity of Tunnel Boring
 Machine launch, and spoil removal





PORT OF MIAMI TUNNEL - FLORIDA










PORT OF MIAMI TUNNEL - FLORIDA

- (2) 39 ft ID x 4,200 ft Long Transportation Tunnels
- 120 ft deep
- Completion May 2014
 - On schedule
 - Within budget
- Challenges
 - Porous coral and limestone required grouting, restricted access above tunnel due to shipping channel





BLUE PLAINS TUNNEL PROJECT DISTRICT OF COLUMBIA








BLUE PLAINS TUNNEL PROJECT

- 23 ft ID x 24,200 ft CSO Tunnel
- 160 ft deep
- Completed Dec 2015
 - 3 months ahead of schedule
 - Under budget
- Challenges
 - Large deep shafts, existing infrastructure above tunnel






BAY TUNNEL - SAN FRANCISCO





BAY TUNNEL – SAN FRANCISCO

- 15 ft ID x 5 mile water tunnel
- 110 ft deep
- Completed Oct, 2014
 - On schedule
 - Within budget
- Challenges
 - Long tunnel drive, no
 intermediate shafts, limited
 surface access, and high ground
 water pressure





WILLAMETTE RIVER COMBINED SEWER OUTFALL PROGRAM – PORTLAND










WILLAMETTE RIVER TUNNELS - PORTLAND

- (1) 14 ft ID x 3.5 mile 120 ft deep and (1) 22 ft ID x 6 mile
- 150 ft deep CSO tunnels
- Cost Reimbursable Fixed Fee
- Construction Complete Feb 2012
 8 months ahead of schedule
- Construction value US \$719 M, 9% under budget
- Challenges
 - Schedule, existing infrastructure, groundwater, Tunnel Boring Machine breakout, soil modification, and subcontract changes





GOTTHARD BASE TUNNELS – SWISS ALPS







GOTTHARD BASE TUNNELS-SWISS ALPS

- (2) 30 ft ID x 35 mile rail tunnel
- Up to 6,560 ft deep
- Completed June 2016 within schedule (17 years)
- Final construction cost \$12.5B within budget
- Challenge: Safety, geology
- For the 2 main tunnels and the safety, ventilation and cross cuts, a total of 95 miles tunnel has been bored





SR-99 ALASKAN WAY REPLACEMENT-SEATTLE





SR-99 ALASKAN WAY TUNNEL-SEATTLE


- 53 ft ID x 2 mile transportation tunnel
- Construction schedule
 - Approximately 2 year delay
- Challenges
 - Equipment malfunction, existing pile foundations and other infrastructure, difficult ground







SEATTLE TUNNEL SUCCESS





LESSONS LEARNED

- Proactive risk management strategy at all stages
- Assign risk to appropriate party
- Select project delivery method to maximize project benefits
- Get construction input early
- Invest in good geotechnical program and GBR
- Must have strong owner involvement
- Co-locate project team
- Resolve Right-of-Way and property acquisition early
- Resolve utility issues early
- Identify long lead items early
- Proactively manage logistical issues
- Develop effective program communication strategy



QUESTIONS



The California WaterFix

April 2015 Construction Cost Estimate





Today's Presentation

- 1. 5RMK Qualifications/experience
- 2. Scope of program
- 3. Cost summary
- 4. Basis of estimate
- 5. Intakes
- 6. Clifton Court pump plants
- 7. Tunnel reaches

1. 5RMK Qualifications

5RMK Is a project management and planning organization providing the following services to the infrastructure and resource development industries:

- Estimating, scheduling, project planning
- Permitting, siting assessments, environmental compliance
- Program & construction management
- Claims support, defense & dispute resolution



1. 5RMK Qualifications















China National Coal Group Corp



2. Scope of 2015 Estimate

- New class 3 estimate as defined by the Association for The Advancement of Cost Engineering International
- New scope definition based on new quantity take-offs, crew definitions, equipment selections and productivities
- Scope of the Project:
 - 3 3000 CFS Intakes
 - 2 4500 CFS Clifton Court Pump Plants
 - 1 Intermediate Forebay
 - 1 Clifton Court modifications, include embankments, siphons, canals and control structures
 - Tunnels with shafts and safe havens
 - 1- 28 ft inside diameter x 2 mile long (reach 1)
 - 1 28 ft inside diameter x 4.8 mile long (reach 3)
 - 1 40 ft inside diameter x 6.8 mile long (reach 2)
 - 2 40 ft inside diameter x 30.1 mile long (reaches 4-7)

2. Scope of 2015 Estimate

Total constructed value includes:

- All craft labor costs
- Construction equipment operating and ownership cost
- All permanent material and supply cost
- Field offices, laydown and staging area development
- Personnel, material, equipment and other transport cost
- Construction supervision, administration and management

Cost does not include:


Land Acquisition, Program Management, Construction Management,
 Engineering, or Contingency

4. Basis of Estimate

- Based on April 1, 2015 Conceptual Engineering Report (CER)
- Detailed quantity takeoffs prepared from CER
- Wage & workmen's comp rates based on "prevailing rates" listed by California
 Department of Industrial Relations
- Equipment ownership and operating costs based on US Army Corps Engineers
- Vendor and subcontract costs based on independent supplier solicitations
- All costs data is in 2014 dollars.
- Work shifts surface facilities: 4 days per week, 10 hours per day
- Work shifts tunnels: 5 days per week, (2)10 hours shifts per day
- Geotechnical data is limited further investigations are planned
- ♦ Advance rate for 40' diameter tunnels 31.1 to 34.1 ft/day
- Advance rate for 28' diameter tunnels 34.5 ft/day (reach 1); 40.4 ft/day (reach 2)



7. Tunnel Reaches





3. Construction Cost

CWF April 2015 Estimate Summary

Contract	Estimate
Intakes 2,3, 5	\$ 1,082,880,306
Intermediate Forebay	\$ 159,579,782
Clifton Court Forebay	\$ 593,720,041
Clifton Court Pump Plant	\$ 446,577,237
Reach 7 Tunnels	\$ 1,538,449,966
Reach 6 Tunnels	\$ 1,559,673,985
Reach 5 Tunnels	\$ 899,619,545
Reach 4 Tunnels	\$ 1,603,383,401
Reach 1, 2, & 3 Tunnels	\$ 1,218,681,541
Communication Network, Scada	\$ 25,065,734
Access, Power Delivery & Utility Relocations	\$ 371,300,000
Construction Total	\$ 9,498,931,538

Estimate Summary

Item	5RMK Estimate ^{(1),(2)} (Billions)
Construction	\$9.50
Contingency	\$3.38
Construction Subtotal	\$12.88
PM/CM/Eng	\$1.91
Land acquisition	\$0.15
Grand Total	\$14.94

- (1) Program estimates in 2014 dollars
- (2) ~36% Contingency on construction

California WaterFix







Questions?

ALDEA SERVICES


CALIFORNIA WATER FIX

RISK MANAGEMENT – DESIGN AND CONSTRUCTION



US Guidelines Exist for Risk Management on Tunnel Projects

- US Risk Management practice established by this document
- Published and available online by Underground Construction Association of Society for Mining, Metallurgy, and Exploration
- Emphasizes:
 - The importance of experience in project team
 - The use of Risk Registers as a risk management tool
 - Consistent risk management approach from early planning throughout life of project



http://www.smenet.org/SME/media/UCA/Resources/SME3409-GIRM-Report-Booklet-WEB.pdf

Process of Risk Management




Three-Step Risk Management Process

AVOID MITIGATE 3 **ALLOCATE** Change tunnel Probe ahead Provide clear alignment to and grout to contractual mitigate risk avoid baselines to from faults structures allocate residual risk

Design and Construction Risks

Probability Rating	AKA	
5	Probable	0
4	Likely	onse
3	Possible	Consequence
2	Unlikely	Ф
1	Improbable	



Design and Construction Risks


Risk Examples – Top Five

☐ Initial works delayed leading to consequent delays to main construction	
☐ Geotechnical investigation delayed leading to delay in design completion and start of construction	
☐ Transmission power delayed leading to delay to start of tunneling	
☐ Differing geotechnical conditions leading to slower progress, increased cost and delay to completion of tunneling	
☐ Substantial design change required during construction leadin to delay in commissioning	g


Program Estimate

Item	5RMK Estimate (Billions)
Estimated Base Construction Cost	\$9.50
Contingency	\$3.38
Program Management/Construction Management/Engineering	\$1.91
Land Acquisition	\$0.15
Grand Total	\$14.94


Annual Expenditures – 2014 Dollars



Annual Expenditures – with Risk and Inflation Cost



California WaterFix Construction Cost Distribution Profile



Estimate Summary

Item	Risk with Mitigation at 75% Confidence Interval ⁽¹⁾⁽³⁾ (Billions)	5RMK Estimate ^{(1),(2)} (Billions)	Jacobs Eng Estimate ^{(1),(2)} (Billions)
Construction	\$10.66	\$9.50	\$8.86
Contingency	_	\$3.38	\$3.15
Construction Subtotal	\$10.66	\$12.88	\$12.01
PM/CM/Eng	\$1.91	\$1.91	\$1.91
Land acquisition	\$0.15	\$0.15	\$0.15
Grand Total	\$12.72	\$14.94	\$14.07

- (1) Program estimates in 2014 dollars
- (2) ~36% Contingency on construction for 5RMK and Jacob Engineering estimates
- (3) Based on risks known at time of assessment

Questions?